

NOTICE INVITING QUOTATION

Date: 15/11/2017

Sealed item rate quotation are hereby invited from the approved contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for Development of area like concrete flooring, tile flooring and misc work near GCR at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Name of work: Development of area like concrete flooring, tile flooring and misc work near GCR at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Estimated Cost: Rs.2,27,890/-

Cost of Tender: Rs.500/- (non-refundable) in form of DD in favor of '**Principal, Satyawati College**'.

Time period for completion of the work: 2 months from the seventh day of issue of award letter/work order.

Date of receiving of tender document upto: 08.12.2017 at 2.30 p.m.

Date of opening tender document: 08.12.2017 at 3.30 p.m.


Earnest Money: Rs.4,500/- in form of CDR, DD in favor of '**Principal, Satyawati College**'.

Tender opening/receiving authority: Principal, Satyawati College, Ashok Vihar, Delhi

Undertaking:

I/We hereby quote item rate/percentage rate _____ above/below/ at par on the estimated cost of Rs.2,27,890/-

Signature of Contractor


Signature of Principal

I/We hereby undertake our agency have not been black listed/debarred in any government/semi-government organization since last three years.

Signature of Contractor

Conditions:

1. No conditional tender will be accepted
2. College authority reserves the right to accept or reject any or all tenders without assigning any reason thereof.
3. CPWD specification will be followed with up-to-date correction slip.
4. Rate quoted will be in figure and words.
5. 1.5% water charge will be recovered from the gross amount of work done.
6. No deviation/extra item/substitute item shall be carried out without the approval/sanctioning of the competent authority.
7. Payment will be made after due satisfaction of competent authority.
8. Taxes as applicable from time to time will be deducted from the gross amount of bill.
9. The material used in the work got approved from the competent authority. Without sample approval the work seems to be rejected and no payment will be made for.
10. The tender papers will be considered with relevant documents like registration of contractor, PAN card, GST.

ESTIMATE

Name of Work:Development of area like concrete flooring,tile flooring and misc work near GCR at Satyawati College, Ashok Vihar, Phase-III, Delhi

S.No.	Description	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil.	10.00	cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	9.00	cum		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	9.00	cum		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	12.00	cum		
5	15 mm cement plaster on rough side of single or half brick wall of mix :1:6 (1 cement: 6 coarse sand).	80.00	sqm.		
6	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :Old work (one or more coats).	100.00	sqm.		
7	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigments etc., complete.	50.00	sqm.		
11		1.00	each		
8	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.75 mm diameter.	5.00	each		

9	<p>Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5</p>	2.00	each		
10	<p>Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.</p>	10.00	cum		
TOTAL					