

NOTICE INVITING QUOTATION

Date: 26/09/2017

Sealed percentage rate quotation are hereby invited from the approved contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for Development of Cycle Stand Area at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Name of work: Development of Cycle Stand Area at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Estimated Cost: Rs.8,16,000/-

Time period for completion of the work: 3 months from the seventh day of issue of award letter/work order.

Date of receiving of tender document upto: 24.10.2017 at 1.00 p.m.

Date of opening tender document: 24.10.2017 at 3.30 p.m.


Earnest Money: Rs.16,500/- in form of CDR, DD in favor of '**Principal, Satyawati College**'.

Tender opening/receiving authority: Principal, Satyawati College, Ashok Vihar, Delhi

Undertaking:

I/We hereby quote item rate/percentage rate _____ above/below/ at par on the estimated cost of Rs.8,16,000/-

Signature of Contractor


Signature of Principal

I/We hereby undertake our agency have not been black listed/debarred in any government/semi-government organization since last three years.

Signature of Contractor

Conditions:

1. No conditional tender will be accepted
2. College authority reserves the right to accept or reject any or all tenders without assigning any reason thereof.
3. CPWD specification will be followed with up-to-date correction slip.
4. Rate quoted will be in figure and words.
5. 1.5% water charge will be recovered from the gross amount of work done.
6. No deviation/extra item/substitute item shall be carried out without the approval/sanctioning of the competent authority.
7. Payment will be made after due satisfaction of competent authority.
8. Taxes as applicable from time to time will be deducted from the gross amount of bill.
9. The material used in the work got approved from the competent authority. Without sample approval the work seems to be rejected and no payment will be made for.
10. The tender papers will be considered with relevant documents like registration of contractor, PAN card, GST.

Name of Work: Development of cycle stand area at Satyawati College, Ashok Vihar, Phase-III, Delhi

Schedule of Quantity

S.No.	Description	Quantity	Unit	Rate	Amount
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. All kinds of soil	540	100 sqm		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	2.1 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size	108	cum		
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	540	sqm		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: (4.1)Cement mortar 1:4 (1 cement : 4 coarse sand)	4	cum		
	TOTAL				