

NOTICE INVITING QUOTATION

Date: 23/05/2017

Sealed percentage rate quotation are hereby invited from the approved contractor enlisted with CPWD, MES, Railways and working contractor of Delhi University for Construction of Septic tank for nursery toilet at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Name of work: Construction of Septic tank for nursery toilet at Satyawati College, Ashok Vihar, Phase-III, Delhi.

Estimated Cost: ₹ 40,552/-

Time period for completion of the work: 15days from the seventh day of issue of award letter/work order.

Date of receiving of tender document : 09.06.2017 at 3.00 p.m.

Date of opening tender document: 09.06.2017 at 3.30 p.m.


Earnest Money: ₹1000/- in form of CDR, DD in favor of '*Principal, Satyawati College*'.

Tender opening/receiving authority: Principal, Satyawati College, Ashok Vihar, Delhi

Undertaking:

I/We hereby quote item rate/percentage rate _____ above/below/ at par on the estimated cost of ₹ 40,552/-

Signature of Contractor


Signature of Principal

I/We hereby undertake our agency have not been black listed/debarred in any government/semi-government organization since last three years.

Signature of Contractor

Conditions:

1. No conditional tender will be accepted
2. College authority reserves the right to accept or reject any or all tenders without assigning any reason thereof.
3. CPWD specification will be followed with up-to-date correction slip.
4. Rate quoted will be in figure and words.
5. 1.5% water charge will be recovered from the gross amount of work done.
6. No deviation/extra item/substitute item shall be carried out without the approval/sanctioning of the competent authority.
7. Payment will be made after due satisfaction of competent authority.
8. Taxes as applicable from time to time will be deducted from the gross amount of bill i.e. VAT 4%, Income Tax 2%, Work Labour Cess 1%.
9. The material used in the work got approved from the competent authority. Without sample approval the work seems to be rejected and no payment will be made for.
10. Electrical works are to be carried out through license holder.
11. The tender papers will be considered with relevant documents like registration of contractor, PAN card, VAT, Service Tax etc (if applicable).

ESTIMATE

Name of Work: Construction of Septic tank for nursery toilet at Satyawati College, Ashok Vihar, Phase-III, Delhi

S.No.	Description	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	10	cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size)	0.5	cum		
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	0.5	cum		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	4	cum		
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	70	kg		
6	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	40	sqm.		
7	Distemping with dry distemper of approved brand and manufacture (two or more coats) of required shade on new work, over and including water thinnable priming coat to give an even shade	20	sqm.		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	10	sqm.		
9	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	10	cum		
TOTAL					