

सत्यवती महाविद्यालय Satyawati College

(दिल्ली विश्वविद्यालय) (University of Delhi) NAAC ACCREDITED 'A+' GRADE



NAME ACCREDITE

Ref. No. SC/ADMN. 1661 /2025

20/0/ko 95

Notice for Inviting Spot Quotations

Percentage rate spot quotations are here by invited from contractors enlisted with CPWD, MES, Railways and working contractors of University of Delhi for the work of "-Making provision of sun shade near channel gate entry in Old Building at Satyawati College, University of Delhi" so as to reach the college office by 1.00 p.m. on 23.01.2025.

S.No	Description of item	Unit	Qty	Rate	Amount
1	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. M.S. tube	kg	100.00	196.80	19680.00
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work including over an under coat of suitable ordinary paint	sqm	6.00	226.25	1357.50
3	Cutting holes up to 30x30 cm in walls including making good the same: With common burnt clay F.P.S. (non modular) bricks	each	4.00	416.80	1667.20
4	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge.	sqm	35.00	338.25	11838.75
5	P/F fibre sheet (4 mm thick) roofing wall putty coated J or L hooks nots and bolts etc complete.	sqm	6.50	2198.96	14293.24
				Total	48836.69

Conditions:

- 1. The work is to be carried out as per CPWD specifications.
- 2. The time allowed completing the work 5 days.
- 3. No water charges to be deducted from the bill
- 4. The rates quoted should be inclusive of all taxes and duties & should be written both in words and figure.
- 5. The contractor should see the site before quoting the rate.

6. Undersigned reserves the right to reject any or all the quotation without assigned any reason thereof.

Principal

Mac

I par the estimate

		NEK
I/we	hereby agree to execute the @	% above/ below at par the estimate
cost.		