



सत्यवती महाविद्यालय Satyawati College

(दिल्ली विश्वविद्यालय)
(University of Delhi)

NAAC ACCREDITED 'A+' GRADE



Ref. No. SC/ADMN.16601 2025

20/01/2025

Notice for Inviting Spot Quotations


Percentage rate spot quotations are here by invited from contractors enlisted with CPWD, MES, Railways and working contractors of University of Delhi for the work of "Replacement of broken glass panes, looking mirror and repair of windows etc. at Satyawati College, University of Delhi" so as to reach the college office by 1.00 p.m. on 23.01.2025.

S.No.	Description of item	Unit	Qty.	Rate	Amount
1	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	sqm	9.00	1090.65	9815.85
2	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	each	9.00	1607.95	14471.55
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	sqm	6.50	1505.25	9784.13
4	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge.	sqm	20.00	338.25	6765.00
5	Repair of aluminum window i/c taking out, with EPDM gasket, aluminum angels, screws etc. Complete & refixing the same in all respect as per the direction of Engineer-in-charge.	each	10.00	882.67	8826.70
				Total	49663.23

Conditions:

1. The work is to be carried out as per CPWD specifications.
2. The time allowed completing the work 5 days.
3. No water charges to be deducted from the bill
4. The rates quoted should be inclusive of all taxes and duties & should be written both in words and figure.
5. The contractor should see the site before quoting the rate.
6. Undersigned reserves the right to reject any or all the quotation without assigned any reason thereof.

I/we _____ hereby agree to execute the @ _____ % above/ below at par the estimate cost.


Principal

Signature of the Contractor

Name _____

Address _____

Contact No. _____