

## सत्यवती महाविद्यालय Satyawati College

(दिल्ली विश्वविद्यालय) (University of Delhi)



**NAAC ACCREDITED 'A+' GRADE** 

Ref. No. Sc/Admin/420/2025

01/09/2025

## **Notice for Inviting Spot Quotations**

Percentage rate spot quotations are here by invited from contractors enlisted with CPWD, MES, Railways and working contractors of University of Delhi for the work of "Repair of Toilets in Auditorium" so as to reach the college office by 2.00 p.m. on 02.09.2025.

| S.No | Description of item   | Unit | Qty  | Rate    | Amount  |
|------|---|------|------|---------|---------|
| 1.   | Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete.  | Sqm  | 6.50 | 1475.35 | 9589.77 |
| 2.   | Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 meters lead.   | Sqm  | 6.50 | 54.65   | 355.22  |
| 3.   | Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: W.C. pan with ISI marked white solid plastic seat and lid | Nos  | 2.00 | 8006.6  | 16013.2 |
| 4.   | Dismantling W.C Pan of all sizes including disposal of dismantled materials including melba all complete as per directions of Engineer-in-Charge  | Nos  | 2.00 | 134.10  | 268.20  |
| 5.   | Providing and fixing CP brass health faucet 15 mm nominal bore and premium quality including wall outlet with shower hook in round shape,5.5. Fluxtube 1.2 m long with Nuts etc.  | Nos. | 2.00 | 1000    | 2000    |
| 6.   | Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.   | Nos. | 2.00 | 820     | 1640    |

|     | Providing and fixing wash basin with C.I. brackets, 15 mm C.P.                           | Nos.  | 1.00               | 2196.05 | 2196.05  |  |
|-----|--|-------|--------------------|---------|----------|--|
| 7.  | brass pillar taps, 32 mm C.P. brass waste of standard pattern,                           |       |                    |         |          |  |
|     | including painting of fittings and brackets, cutting and making                          |       |                    |         |          |  |
|     | good the walls   |       |                    |         |          |  |
|     | wherever require:  |       |                    |         |          |  |
|     | Providing and laying vitrified floor tiles in different sizes                            | Sqm   | 2.78               | 1533.45 | 4262.99  |  |
| 8.  | (thickness to be specified by the manufacturer) with water                               |       |                    |         |          |  |
|     | absorption less than 0.08% and conforming to IS: 15622, of                               |       |                    |         |          |  |
|     | approved make, in all colors and shades, laid on 20mm thick                              |       |                    |         |          |  |
|     | coment mortar 1:4 (1 cement: 4 coarse sand), jointing with grey                          |       |                    |         |          |  |
|     | cement slurry @ 3.3 kg/sqm including grouting the joints with                            |       |                    |         |          |  |
|     | white cement and matching pigments   |       |                    |         |          |  |
|     | etc., complete. Size of Tile 600x600 mm  |       |                    |         |          |  |
|     | to a second loid in coment mortar  | Sqm   | 2.78               | 73.40   | 204      |  |
| 9.  | Dismantling tile work in floors and roofs laid in cement mortar                          |       |                    |         |          |  |
|     | including stacking material within 50 meters lead. For thickness of tiles 10 mm to 25 mm |       |                    |         |          |  |
|     |  | Nos   | 1.00               | 455     | 455      |  |
| 10. | Washbasin fastener   | 1,105 |                    |         |          |  |
|     |  |       |                    |         | D 26094/ |  |
|     |  |       | Total Rs. 36984 /- |         |          |  |

## Conditions:

- 1. The work is to be carried out as per CPWD specifications.
- 2. The time allowed completing the work 2 days.
- 3. No water charges to be deducted from the bill
- 4. The rates quoted should be inclusive of all taxes and duties & should be written both in words and

5. The contractor should see the site before quoting the rate.

6. Undersigned reserves the right to reject any or all the quotation without assigned any reason thereof.

Principal hereby agree to execute the @ \_\_\_\_\_\_% above/ below at par I/we the estimate cost.

> Signature of the Contractor Name Address Contact No.\_\_\_\_