

## सत्यवती महाविद्यालय Satyawati College

(दिल्ली विश्वविद्यालय) (University of Delhi)



NAAC ACCREDITED 'A+' GRADE

Ref. No. 80/Admn/06/2025

Dated: 03.04.2025

## **Notice for Inviting Spot Quotations**

Percentage rate spot quotations are here by invited for the work of" "Repair of leakage in existing shed and provision of sheet back side of lockers in Staff Room at Satyawati College" So as to reach the office of the undersigned up to 1.00 PM on 07.04.2025.

S. No.	Description of item	Unit	Qty.	Rate	Amount
1.	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 10.25.1 In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	kg	20.00	196.80	3936.00
2.	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement: 3 fine sand) as per standard design: 12.21.1 In 75x75 mm deep chase	metre	18.00	305.15	5492.70
3.	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zine coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	25.00	738.65	18466.25
4.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work including over an under coat of suitable ordinary paint	sqm	50.00	226.25	11312.50

Page: 1 of 2

Scanned with OKEN Scanner

5.	Cutting holes up to 30x30 cm in walls including making good the same: With common burnt clay F.P.S. (non modular) bricks	each	4.00	416.80	1667.20
6.	Making chases up to 7.5x7.5 cm in walls including making good and finishing with matching surface after housing G.I. pipe etc	metre	18.00	202.90	3652.20
7.	Taking out, repair and refixing the end portion of the existing shed with necessary additional fibre sheet as required at site making leak proof complete as per direction (chase and gola if required to be paid for separately)	job	2.00	2000.00	4000.00
	Total				48,526.85.00/-

## **Conditions:**

- 1. The work is to be carried out as per CPWD specifications.
- 2. The time allowed completing the work 5 days.
- 3. No water charges to be deducted from the bill
- 4. The rates quoted should be inclusive of all taxes and duties & should be written both in words and figure.
- 5. The contractor should see the site before quoting the rate.
- 6. Undersigned reserves the right to reject any or all the quotation without assigned any reason thereof.

	Principal
I/we	hereby agree to execute the @% above/ below at par
the estimate cost (Annexure-A).	
	- Signature of the Contractor
	NameAddress
	Contact No.

Page: 2 of 2