



सत्यवती महाविद्यालय Satyawati College (दिल्ली विश्वविद्यालय) (University of Delhi)



वसुधैव कुटुम्बकम्
ONE EARTH • ONE FAMILY • ONE FUTURE

NAAC ACCREDITED 'A+' GRADE

Notice Inviting Quotation

Ref. No.SC/ ADMN./477/2023

06.10.2023
Dated: 03.10.2023

Sealed percentage rate quotations are hereby invited from the empanelled contractors of Satyawati College for the work "Providing and laying floor tiles, Window blinds and repair/finishing work in Room no-10, Ground Floor, Satyawati College" So as to reach the office of the undersigned up to 3.00 PM on 10.10.2023

S.NO	Item	Unit	Qty	Rate	Amount
1	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m Initial lead, for all leads including all lifts involved.	cum	4	219.35	877
2	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm.	sqm	2	1537.4	3075
3	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints size 600x600mm	sqm	12	1676.15	20114
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work	sqm	6	131.45	789
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc.	sqm	60	20.85	1251.00
6	Distemping with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification	sqm	60	92.75	5565.00
7	Providing and fixing roller blinds (sun screen) / black out of approved quality (Meck / Deck/ Vista) or equivalent to deck 5000 regular series as approved.	sqm	1.5	2450.00	3675.00
8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	sqm	50	70	3500
9	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	sqm	60	60.00	3600.00
10	Repair of Door shutter i/c cutting to the required height and making good the same with edge moulding etc complete as per the direction of the Engineer-in-Charge.	each	1	700	700
				Total	43146

Condition:-

1. The work should be completed in 7 days.
2. 1.50 % water/Electric charges will be deducted.
3. Rates should be quoted both in words & figures.
4. Undersigned reserves the authority to reject any or all the quotation without assigning any reason therefore

I/we hereby quote.....% above/ below/ at par on the estimated cost of Rs.43,146/-
Undertaking I/we hereby undertake that my/our agency have not been black listed/debarred in any Govt. organization since last 3 years.

(Contractor)

Copy to

1. College website
2. Notice Board

Ashok
Principal

Ashok
Principal